

## PROJECT APPENDIX A - 1

### PRE-ASSEMBLED & PORTABLE BUILDINGS

All pre-assembled and portable classroom buildings located on state property or used by any governmental board, commission, agency, body, authority, instrumentality, department, or subdivision of the state shall:

- A. Be installed by a certified installer;
- B. Possess a Manufactured Housing Commission label.

The submission of a site plan and other applicable drawings and specifications shall be forwarded to the Technical Staff for plan review when locating or relocating these structures. Use DCM Form B-1: Transmittal of Plans and/or Specifications when submitting documents for review. These drawings shall (at a minimum) delineate the following:

- A. Locations and distances between units and adjacent structures.
- B. Utility (water, sewer, power, fire alarm, etc.) connection/service.
- C. Accessibility provisions (ADA Standards) to the structures (ramps, walks, handrails, etc.).
- D. Adequate restroom facilities.

**Note:**

Schematic and Preliminary Reviews are not required for these projects. A Final Plan Review is required. A DCM B-1 Form: Transmittal of Plans and/or Specifications and a Final Plan Review Fee is required for a Final Review.